BRUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Executive Engineeer Dasarahalli Division B.B.M.P, Bangalore - 73

SCHEDULE - B

Name of the Work :Constructoin of compound to Indira canteen at pipeline road in Ward no 13 Shettyhalli Sub Div

Sl. No.	Description	Unit	Qty	Rates	
				In Figures	In Words
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	77.13	205.00	Two Hundred Five Only
2	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed concrete laid in layers not exceeding 15cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery.	Cum	10.62	5450.00	Five Thousand Four Hundred Fifty Only
3	Providing and constructing granite / trap / basalt size stone masonry in **Superstructure with cement mortar 1:4**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	49.19	4500.00	Four Thousand Five Hundred Only
4	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chisle dressed in courses not less than 15 cms high, bond stones at two m apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	20.88	5400.00	Five Thousand Four Hundred Only
5	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specificationsand directions of engineer in charge of the work.	Sqm	39.33	100.00	One Hundred Only
6	Providing and laying in position plain cement concrete of **mix 1:2:4 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregares @ 0.69 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4.95	5800.00	Five Thousand Eight Hundred Only
7	Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification and directions of engineer in charge of the work	Tonne	0.25	65400.00	Sixty Five Thousand Four Hundred Only

Executive Engineer

Contractor Signature

Signature of the Contractor

Executive Engineer

Scanned by CamScanner